ATTACHMENT A

MATERIAL REQUISITION

FOR

COLUMN INTERNALS

(103-C-101 / 103-C-201)

JOB NO.:	**POGC-760-81-156**
DOC. NO.:	**DI-6340S-0510-OI-0040**
CLIENT:	**N.I.O.C – PARS OIL & GAS COMPANY**
LOCATION:	**ASSALUYEH, IRAN**

REV.	DATE	DESCRIPTION	ORIGIN	PRPD	CHKD	APPD	AUTH
0	MAR.10,'04	ISSUED FOR PROCUREMENT	O.I.E.C	M.R.M	M.KH	R.M	H.R

TABULATION OF REVISED PAGES

PAGE	REV. 1	REV.2	REV.3	REV.4	REV.5
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					

PAGE	REV. 1	REV.2	REV.3	REV.4	REV.5

TABLE OF CONTENTS

1. EQUIPMENT AND/OR MATERIALS INQUIRED : 4

2. DOCUMENTS ATTACHED TO THIS REQUISITION : 4

3. DEVIATIONS FROM PURCHASER'S REQUIREMENTS : 6

4. SCOPE OF SUPPLY: 6

5. SCOPE OF WORK: 8

6. APPLICABLE CODES & STANDARDS: 9

7. DOCUMENTS REQUIRED AFTER PURCHASE ORDER: 9

8. INSPECTION AND TESTS: 9

9. COORDINATION MEETING: 9

10. DUTY AND RESPONSIBILITY OF THE VENDOR SUPERVISOR: 9

11. SPECIAL NOTES AND OTHERS: 10

Special NOTE: "Vendor" in this document means "sub-supplier" which shall remain the responsibility of the Columns Manufacturer.

ATTACHMENT

1. VENDOR DOCUMENTS REQUIREMENTS (REV. 0)
2. SPECIFIC JOB REQUIREMENTS (REV. 0)
3. LIST OF SUB-VENDORS (REV. 0)

Please develop quotation for following equipment and/or materials in strict accordance with conditions stated in this Requisition and any attached documents. Exceptions, deviations and alternatives will be valid only if approved in writing by PURCHASER. Articles marked with "X" hereunder are applied as conditions of this Requisition.

1. EQUIPMENT AND/OR MATERIALS INQUIRED:

NO.	EQUIPMENT NO.	ITEM	SETS	DESCRIPTION
1	103-C-101/201	1	2	INTERNALS FOR Condensate Stabiliser
	TOTAL	1	2	

2. DOCUMENTS ATTACHED TO THIS REQUISITION :

The following documents shall form an integral part of this Requisition. And in case of conflicts between requirements, as a general rule, the most restrictive requirements shall govern.

[X] Vendor Documents Requirements (Rev. 0)

[X] Specific Job Requirements (Rev. 0)

[X] Drawings

Table 1: List of Drawings

NO.	DRAWING NO.	REV.	DRAWING TITLE
1	DW-6340S-103-0510-0101	4	ENGINEERING DRAWING FOR 103-C-101/201

[X] DATA SHEETS FOR EQUIPMENT AND/OR MATERIALS INQUIRED

TABLE 2: List Of Data Sheets

NO.	DATA SHEET NO.	REV.	DOCUMENT TITLE
1	SPP-6340S-103-C-0101	6	PROCESS DATA SHEET FOR 103-C-101/201
2	NC-6340S-103-0801-0009	3	NOTE OF CALCULATION FOR 103-C-101/201

[X] Applicable Engineering Specifications and/or Documents

Table 3: List of Applicable Engineering Specifications and/or Documents

NO	DOCUMENT NO	REV.	DOCUMENT TITLE
1	DB-6340S-999-P332-203	6	LIST OF APPLICABLE CODES AND INDUSTRY STANDARDS
2	DB-6340S-999-P312-205	3	PROCESS SIZING CRITERIA
3		-	EQUIPMENT AND MATERIAL CERTIFICATE

NO	DOCUMENT NO	REV.	DOCUMENT TITLE
4	RP-6340S-999-0400-001	7	DESIGN AND FABRICATION OF PRESSURE VESSELS
5	RP-6340S-999-0400-002	8	DESIGN AND FABRICATION OF PRESSURE VESSELS ACCORDING TO PD 5500
6	RP-6340S-999-0400-005	8	STANDARD DRAWINGS FOR ACCESSORIES & EQUIPMENT OF VESSELS
7	RP-6340S-999-0400-006	4	CHECK LIST FOR INSPECTION OF PRESSURE VESSELS
8	RP-6340S-999-0400-007	4	INSPECTION PROCEDURE FOR PRESSURE VESSELS
9	RP-6340S-999-0570-001	5	VESSEL TRAYS AND ASSOCIATED HARDWARE
10	RP-6340S-999-6300-001	3	WELDING OF PRESSURE CONTAINING PIPING AND EQUIPMENT.JOB SPEIFICATION
11	RP-6340S-999-6300-005	3	WELDING OF UNS 31254 ALLOY
12	ONS-01-0-PR-0001	B	VENDOR DOCUMENTS HANDLING PROCEDURE FOR ONSHORE FACILITIES
13	COM-07-3-PR-0004	A	PROCEDURE FOR SHOP INSPECTION AND TESTING
14	COM-07-3-PR-0005	A	INSTRUCTION FOR PACKING, MARKING AND SHIPPING
15	COM-01-3-PR-0001	0	DOCUMENT IDENTIFICATION PROCEDURE

[X] Others:

[X] Recommended Vendor List

[X] Inspection and Test Plan

3. DEVIATIONS FROM PURCHASER'S REQUIREMENTS :

Vendor's quotation shall be in strict conformity with Purchaser's requirements. Unless exceptions, deviations or alternatives are clearly identified or listed in Vendor's quotation, the requirements and conditions in this Requisition shall be deemed to be accepted by VENDOR.

4. SCOPE OF SUPPLY:

Vendor shall be responsible for the design works, supply of materials, fabrication, shop assembling, shop inspection and tests, guarantee, painting, packing, transportation and satisfactory operation of the entire unit to the extent of the Vendor's supply.

NOTE: Supply of internals includes but is not limited to below items:
(X) Trays (including but not limited to tray floors complete of weirs, down comers, major beams, false down comers, tray decks, valve or bubble units, tray deck support beams, seal pots/pans, draw off pots, etc.)
X) Suitable Internal pipe distributer for tray nozzles as required
X) Gas/liquid inlet distributors as required
X) All required hardware such as bolts, nuts, washers, clamps, trusses, and gaskets for internals
X) All sealing materials necessary for final installation (e.g. for chimneys)
X) Special tools and fittings for site assembly, operation and maintenances
X) Temporary caps and covers for internal distributors required for shipping
X) Provisions for longtime storage
X) All necessary devices for transportation (including nozzle covers, bolts, nuts …).
X) Other accessories where needed as per manufacturer standard procedures for proper hydraulic and mechanical performance

Purchaser's approval shall in no way be construed as relieving Vendor of any of his obligation, responsibilities or liabilities under the CONTRACT and/or applicable Codes and Standards.

Should Purchaser fail to comment, or only partially comment, upon Vendor document, this shall not be construed as an acceptance of the content of such document unless expressly provided otherwise. Vendor's quotation shall include, but not be limited to, equipment, materials specified in the following: Articles marked with "X" hereunder shall be within Vendor's Scope of Supply.

[X] VALVE TRAY & DOWNCOMER (with Accessories) listed in Paragraph1

[X] DOWNCOMER / FALSE DOWNCOMER

[X] Liquid Distributor/ Re-distributor

[X] Bed Limiter

[X] BOLTING ASS'Y

[X] Chimney Tray

[X] Grid / Downpipe

[X] Wire Mesh or Demister

[X] Seal Pan/ Draw-off Pan

[X] Inlet Weir

[X] Hardware such as bolts/nuts, washers, clamps and gaskets for internals

[X] Vendor's Standard Accessories

[X] Support beams as required

[X] Spare parts for construction, pre-commissioning, commissioning and start-up

[X] Spare parts for two (2) years operation (as an option)

[X] Special tools for erection & maintenance, like a bolt tensioner, etc., if applicable

[X] Others specified in this specification

[X] Other accessories required for safe operation (not referred in this Specification)

Note
1. For internal feed and draw pipes and deflectors above top tray will be supplied by Vessel Vendor. However, Vendor shall design the pipes and guarantee their performance. Also, they shall be shown on tower attachment drawings.

2. Draw-off sumps for tray and chimney tray will be supplied by Vessel Vendor. However, they shall be designed by Vendor and shown on tower attachment drawings.

3. Adoption of new sub-vendors, from whom the vendor has no experience in purchasing any goods and materials so far, shall be subject to Purchaser's prior approval.The vendor is encouraged to nominate such potential sub-vendors in his Quotation.

NOTE: Scope of work of internals includes but is not limited to below items:
(X) Verification of tray quantity and chimney height (with respect to current exciting valve type)
(X) WPS, PQR, Weld and NDT Map
(X) Reviewing and confirming provided documents and raising conflicts and mismatches for client decision (if any)
(X) Following current nozzle orientations and elevations based on provided documents
(X) Verification of compatibility between instrument device (supplied by others) and tray design for instance clash checking between thermo-well and tray assembly
(X) Leak test for chimney distributer
(X) PMI for non-carbon material

5. SCOPE OF WORK:

1) Scope of Work

Vendor's quotation shall include, but not be limited to, works specified in the following Articles marked with "X" hereunder shall be within Vendor's Scope of Work.

[X] Hydraulic performance calculation and guarantee

[X] Mechanical strength calculation and guarantee

[X] Design of internal feed and draw pipes and deflectors

[X] Review of Vessel Vendor's support drawings

[X] Shop inspection and tests (including trial-assembly of each type trays)

[X] Rust prevention for transportation and long time storage at site

[X] Marking, packing and transportation

[X] Guarantee of the suitability of all used materials (chemical composition, mechanical properties and origin of materials)

[X] Engineering design and documentation as per the requirements of specification

[X] All documents and certificates for Iranian Government approval as required

[X] Vendor shall specify Nace requirements in accordance with MR-0175, where applicable

[X] All materials certificates

[X] All certificates requested in the specification

[X] Trial-assembly of each type trays at column Vendor's shop

[X] Assistance and supervision for installation and pre-commissioning (as an option)

[X] Vendor shall provide assistance and supervision service to Purchaser and ensure the timely presence of all necessary specialists. And, Vendor shall quote separately a per diem rate for attendance.

Note 1. The Design and Construction shall comply with all Regulation of the applicable Governmental Agencies in ***Iran***.

2) Out of Vendor's Scope of Work

(1) Internal installation

6. APPLICABLE CODES & STANDARDS

The list of the applicable Codes & Industry Standards shown on the "List of applicable codes and industry standard (DB-6340S-999-P-332-203 Rev.6)" together with any documents referred to therein shall apply.

The latest edition or revision of codes or standards shall be applied for design & fabrication.

7. DOCUMENTS REQUIRED AFTER PURCHASE ORDER:

All documents and drawings shall be submitted, in accordance with "**VENDOR DOCUMENTS HANDLING PROCEDURE** (Doc. No.: ONS-01-0-PR-0001 Rev.B)" attached in this Requisition.

8. INSPECTION AND TESTS:

Inspection and tests shall be performed by Vendor in accordance with:

[X] Requirements specified in this Requisition and/or any Engineering Specifications attached.

[X] Vendor's proposed procedure subject to Purchaser's Approval

[X] Vendor's ITP approved by PURCHASER

9. COORDINATION MEETING:

After the order is awarded, VENDOR shall, upon receipt of Purchaser's notice, send a sufficient number of qualified personnel to Purchaser's office at Vendor's cost to hold the coordination meeting(s) according to the following schedule:

The first	:	within	2	week(s)	after the order, for	1	day(s)
The second	:	within	3	month(s)	after the order, for	2	day(s)
The third	:	within	_____	month(s)	after the order, for	_____	day(s)
The fourth	:	within	_____	month(s)	after the order, for	_____	day(s)

10. DUTY AND RESPONSIBILITY OF THE VENDOR SUPERVISOR:

10.1 General

The Supervisor, who is dispatched to the site for the installation, start-up, inspection, repair and maintenance of the equipment supplied by the vendor, shall perform his duty for all equipment including those supplied by the vendor's subcontractor.

10.2 Qualification

The Supervisor shall be sufficiently qualified to perform his duty. The vendor shall provide the resume of the expected personnel for Purchaser's approval. Purchaser has a right to reject the Supervisor proposed by the vendor and to appoint alternative personnel.

10.3 Duty

The duty of the Supervisor shall be, but not limited to, as follows;

(1) Witness the inspection of undoing the packing

(2) Check the dimension of the foundation

(3) Supervising and direction for the assembling and installation

(4) Supervising and direction for, and check the leveling and alignment

(5) Supervising and direction for, and check the connection of the main piping

(6) Check the performance, and adjustment of the safety device and instruments

(7) Supervising the preparation of the startup

(8) Supervising and direction for the start-up operation

(9) Execution of and/or supervising and direction for the assembling, disassembling, inspection and repair

(10) Preparation of the inspection record and the miscellaneous report

(11) Advice of the control for the time schedule

(12) Technical supervising and direction for the maintenance

10.4 Responsibility

The vendor shall be responsible to indemnify for damages to property or for personal injuries, which result from the gross negligence of the Supervisor while performing his duty.

11. SPECIAL NOTES AND OTHERS:

11.1 Quotation shall include the following information:

(1) Requisition number

(2) Firm price(s) by item

(3) Earliest delivery date(s)

(4) Origin of material being quoted (country, place, and name of manufacturer)

(5) Approximate shipping weight and dimension

Unpriced quotation should be prepared to be able to meet technical evaluation only.

11.2 The order of priority of documentation is the following:

(1) Data Sheets

(2) This Specification

(3) Other Job Specifications

(4) International Codes and Standards

11.3 No protection, paint or other filling shall be applied to the contract works before they have been inspected, tested and approved. After approval and before dispatch each part of the contract works shall be thoroughly cleaned and appropriately protected and packed in accordance with the requirements of carriers and shippers and suitably for prolonged storage. All packing cases and materials are included in the proposed price, and shall become the property of the purchaser.

11.4 Vendor shall guarantee the operation of the equipment to the specified design conditions. Vendor shall warranty the engineering, materials and workmanship of the equipment for a period of **18** months after successful start-up. Under this warranty, all materials, parts, and assemblies found to be defective during the guarantee period shall be replaced by Vendor. Vendor shall also, if required, supply the services of an experienced engineer to supervise the necessary repairs and replacements.

11.5 Preparation for Shipment

Following testing and inspection, equipment shall be emptied, dried, painted and, where necessary, preserved for shipment and long term outside storage.

Adequate temporary bracing for equipment and accessories shall be provided to avoid overstressing or damage during shipping, transportation and erection, as required.

All equipment shall be packed and weather protected for export. Loose parts shall be boxed and shipped along with an itemized packing list with the main assembly.

11.6 Vendor shall submit the following Vendor Documents within 2 weeks after receiving the Letter of

Intent from Purchaser:

(1) Master Schedule shown design, procurement, fabrication, test, painting, packing & etc.

(2) Vendor shall fill out Vendor Document No., Documents Title, Size/Page, etc in Vendor Document Index & Schedule (VDI) and submit copies of VDI

(3) Loading data for Civil design

(4) General arrangement drawing showing all of dimension and support location detail

11.7 Vendor shall prepare and submit the following documents with **Six (6) copies** inside the packing of the package, separately from VDRS.

(1) Full package of final drawings.

(2) Copy of all certificates.

(3) Inspection release certificate (IRC).

(4) Approved packing list

(5) Calibrated loading data (this calibrated loading data will be used at lifting stage for heavy equipment selection and handling. Therefore, this document shall have a confirmation by CONSORTIUM'S own inspector or an appointed third party inspector before Shipment)

(6) Spare parts list with attachments

11.8 Vendor shall provide the Copy of current certification of ISO 9001/2 or 3. When vendor does not hold ISO certification, vendor shall provide the following documents to purchaser for review

(1) During Equipment/ Material/ Service Procurement/ Subcontracting Stage and, in any way, before Purchase Order:

- Vendor Management commitment letter to Quality
- Detailed Organization Chart of Vendor and Job Ticket scope of work and responsibilities of every position of that chart.
- Name and CV of Personnel for the position shown on the Chart with indication if on pay roll or from Subsidiary or contracted personnel.
- List of working procedure to be issued for the Job at Order / Contractor Stage in order to be as close as possible to ISO 9001/2 or 3 and covering all item of the application Norm.

This list will include as far as possible the existing applicable Vendor working procedure and those to be issued for the job in order to fulfill the applicable Norm.

- Issue of Vendor Management Audit Program

(2) During Equipment / Material Service Purchase Order implementation stage:

- Issue of the Job QA plan
- Issue of working procedures for PURCHASER and COMPANY review within one month after order.
- Implementation of the working procedure during order execution
- Performance of vendor Management Audit Program

Note: Those requirements are applicable for Vendor for which Certification is no more valid and / or under process of certification.

11.9 Vendor shall provide the Copy of vendor quality manual / quality plan.

Quality Plan shall be subject to presentation, discuss and clarification with purchaser, and Company as necessary, prior to incorporation into contract documents, and prior to award of purchase order.

11.10 All packing cases and materials, included in the proposed price are the property of purchaser.

11.11 Vendor shall be legally responsible for hydraulic/Mechanical design and stability/Integrity of the equipment and shall carry out all calculations and check to ascertain for complying with the requirements of codes and project specifications.

11.12 Vendor shall provide a "data book" with documents listed below:

a)General arrangement drawings

b) Sectional shop drawings of the equipment giving all design data requested by the purchaser as well as:

1. Dimension, thickness and materials of the various parts.

2. Fabrication details

3. Position of the center of gravity of the equipment

4. Material certificates with heat no. and test no.

5. Erection procedure

5.1 Quality control plan

5.2 Time schedule

5.3 Erection sequences

5.4 Test schedule

6. Inspection and testing

6.1 Check list

6.2 Dimension check

6.3 Settlement report

7. List of spare parts

11.13 Cost increase as a result of these loading shall be born by vendor.

11.14 Vendor shall separately quote the spare parts necessary for 2 years operation.

11.15 Bidders may supplements their basic quotation with alternative design of significant advantages improving performance, delivery date and etc.

The supply shall include all the items with all the appurtenances and accessories (internal and external) shown on the attached drawings, sketches, standards and requested in this Material requisition and/or necessary for Testing, Shipment, Operation and Maintenance except Items that have been excluded as follows.
VENDOR shall be responsible for Manufacturing, Testing, Inspection, Painting, Packing, Transportation, Spare Parts, Certification, Supply of Goods, Guarantee, and Satisfactory Operation of the entire unit and Documentation in accordance with Specifications, Data Sheets/Engineering Drawings, and other Attachments to the Material requisition

Special Note: (to be confirmed by vendor)
1- Latest revision of DSH/DWGs/CLACs/etc. of equipment that submitted by former vendor/supplier are handed over to bidders along with MR's attachments to be reviewed before PO. So bidder is requested to announce any deviation/alternative of the same before PO to be discussed & Closed. Anyway Mechanical/ Process/Performance guarantee is in vendor scope of work.
2- Handed over documents including DWGs, Data sheets and etc as per Index attachment to be marked up by vendor before PO.
3- Vendor is liable to announce any conflict between drawings/ details shown in handed over DSH/DWGs/ CLACs/etc . also if there is any detail or data indicated in documents which is not feasible in construction point of view, the same shall be announced by vendor before PO.
4- Vendor is responsible to announce any other data as need list including project Documents /DWG/Details, Data sheets, BMS and etc.
5- All Design Standard and Codes for all items, Mechanic, Instrument, Electrical and ... shall be followed latest edition or revision.
6- Since APPROVED DSH/DWG/CLAC/etc. of COLUMN INTERNALS and it's Accessories and that submitted by former vendor/supplier are handed over to bidders along with MR's attachments bidder is requested to submit ITP along with technical proposal to be finalizes at this stage as much as possible.