PROCEDURE

FOR

SHOP INSPECTION AND TESTING

CONTRACT NO. : **POGC-760-81-156**

PROJECT : **SOUTH PARS GAS FIELD DEVELOPMENT (PHASES 9&10)**

COMPANY : **NATIONAL IRANIAN OIL COMPANY**

SITE : **ASSALUYEH / SOUTH PARS GAS FIELD PERSIAN GULF, IRAN**

REV.	DATE	DESCRIPTION	ORIG.	PRPD	CHKD	APP'D	CONTRACTOR's APP'D
A	17/04/2003	For Preliminary Inquiry	LG	HJY			

TABULATION OF REVISED PAGES

PAGE	REV. 0	REV. 1	REV. 2	REV. 3	
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					

PAGE	REV. 0	REV. 1	REV. 2	REV. 3	
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					

TABLE OF CONTENTS

CHAPTER A. GENERAL

CHAPTER B. INSPECTION AND TESTING REQUIREMENTS

CHAPTER C. WORK SCOPE OF TPA

CHAPTER D. MATERIAL AND EQUIPMENT CERTIFICATION

CHAPTER E. INSPECTION COORDINATION PROCEDURE

CHAPTER A. General

1. Scope

This document describes minimum quality requirements for materials and equipment to be supplied by VENDOR and inspection coordination procedure among related parties such as COMPANY, CONTRACTOR, VENDOR or TPA, etc.

2. Terms and Definitions

2.1 COMPANY : Client, NIOC (NATIONAL IRANIAN OIL COMPANY, IRAN)

2.2 CONTRACTOR : Purchaser, CONSORTIUM or any of Consortium members.

2.3 VENDOR :Supplier, A company appointed to supply materials or equipment in accordance with the terms and conditions of a Purchase Order.

2.4 CONTRACTOR's Inspector : Inspector dispatched by CONTRACTOR or inspector of third party inspection agency designated by CONTRACTOR.

2.5 Inspection and Test Plan (ITP) : A document which identifies the main quality control activities (inspection, examination or test, etc.) to be performed during fabrication and manufacturing of equipment and materials. Each activity is designated with Key Code as stated in followings;

2.5.1 Hold Point (H): A designated point during or following a specific activity at which inspection or examination shall not proceed unless the designated parties have witnessed the inspection and/or test.

2.5.2 Witness Point (W): A designated point during or following an important activity at which inspection or examination is required in accordance with the relative procedure. Work may proceed through the designated witness point if the inspector is not present for the previously established activity.

2.5.3 Spot Witness Point (SW): A designated point during or following an activity at which spot inspection or spot examination is required in accordance with the relative procedure. Work may proceed through the designated witness point if the inspector is not present for the previously established activity.

2.5.4 Review Point (R): It is processed through reviewing any results of inspection or test as a method of ensuring that the inspection or test is performed in accordance with any approved drawing, procedure, specifications or acceptance criteria.

2.6 TPA : Third Party Authority assigned by CONTRACTOR for carrying out inspection and certification as a CONTRACTOR's Representative.

2.7 Vendor Quality Document (VQD) : A document set which VENDOR should prepare and submit to CONTRACTOR for review and issue of Release Note before shipment.

3. Referenced Documents

Doc. No.	Title	Rev.
xxxxx	CONSORTIUM's Project Quality Plan : Chapter 8. Shop Inspection and Testing	A
POGC-760-81-156	Contract Document between NIOC and CONSORTIUM	-

4. Inspection Policies

4.1 CONTRACTOR will assign a third party authority (TPA) and/or his own inspector to perform designated inspection activities on behalf of CONTRACTOR. Compensation of TPA's services will be borne by CONTRACTOR. However, in case that a scheduled shop or field test would fall and it must be repeated after the remedy of the failed material or equipment, the additional TPA's and CONTRACTOR's services shall be born by VENDOR's care and cost (traveling and accommodation expenses plus working time of TPA's and CONTRACTOR's inspection)

4.2 VENDOR shall bear any additional costs due to delays that may occur, attributable to the VENDOR, e, g., not readiness to perform the test on the proposed date.

4.3 Such inspection shall not release the VENDOR from performing its own inspection and quality control programs. VENDOR shall incorporate all inspection certificates and/or compliance certificates in VENDOR's final documentation.

4.4 Shop inspection and/or document review shall be carried out by CONTRACTOR and/or his representative and COMPANY at both the point of manufacture and, where necessary, at the source of manufacture sub-ordered materials.

4.5 If equipment has to be modified or repaired in order to pass final inspection and test, VENDOR shall compile a complete dossier containing accurate and detailed records of all design changes, alterations, modifications, adaptations and reasons for them, together with minutes of all relevant meetings and notes of discussions, and shall promptly make such dossier available to CONTRACTOR and COMPANY.

CHAPTER B. Inspection and Testing Requirements.

1. General Requirements for VENDOR Shop Inspection and Testing

1.1 Quality Assurance Plan

VENDOR shall submit his QA plan describing his quality system and its application to the scope of supply complying with the details of inspection level described herein.

This plan shall be in accordance with ISO 9001/9002 standards and the applicable project specification as listed in Attachment.

This quality plan shall cover the following topics but not limited to:

1.1.1 Organization

VENDOR shall provide a description of their QA organization, its resources, and how it is incorporated into his management structure, together with the procedures used to review its effectiveness.

1.1.2 Production schedule

VENDOR shall provide a production schedule indication the key points where quality related manufacturing processes, inspections and tests will occur.

1.1.3 Hold points.

VENDOR shall provide a plan identifying proposed hold points in the production process for witness or approval of particular activities by CONTRACTOR or his appointed agents, and the method of advising CONTRACTOR of the timing of relevant inspections and tests.

1.1.4 Procedure

VENDOR shall provide details of processes and standards by which it is proposed to control:

- ✓ Quality related manufacturing processes, inspections and tests, including sampling techniques,
- ✓ The quality of Sub-VENDOR products,
- ✓ Methods of qualification of work, inspection and test procedures,
- ✓ The quality and identification of in corning material and equipment,
- ✓ The calibration and maintenance of inspection and test equipment,
- ✓ Packing and shipping of finished products,
- ✓ Preparation and supply of specified documentation

1.2 Inspection Documents to be submitted by VENDOR for CONTRACTOR Approval

See “Vendor Document Requirement“

1.3 Tractability Levels

Unless otherwise specifically noted the following certificates in equipment specification sheets and/or relevant specifications, all certificates shall be complied with CHAPTER D.

- EN 10204-3.1C
- EN 10204-3.1B

Note : For type 3.1C and 3.1B applications, the material certificate supplied shall be the original document or a verified copy.

- EN 10204-2.2
- EN 10204-2.3

For centrifugal pumps, material certificates shall be in accordance with EN10204 with a minimum certificate level as follow;

- 3.1B for pressure parts/impeller/shaft
- 3.1B for wearing rings is special materials such duplex is required. Otherwise certificate level is 2.2

Dismantling after test of centrifugal pump is required.

1.4 NDT Qualification

All personnel performing NDT functions must be adequately qualified. The NDT operator’s qualifications shall form part of all manufacturer quality plans and therefore be approved by CONTRACTOR before manufacture takes place. The actual certificates shall be reviewed at the manufacturer works by the inspector.

Note: The manufacturer must bear in mind that the above is also applicable to all sub-manufacturer.

1.5 Pre-Inspection Meeting (PIM)

In case that PIM is required in Inspection Basis, VENDOR shall request to attend PIM at VENDOR’s shop to CONTRACTOR 21 working days in advance. After receiving PIM attendance request from VENDOR, CONTRACTOR will give a notice to related parties including COMPANY, TPA, etc.

VENDOR shall prepare the following documents for the PIM, but not limited to the followings;

- Inspection and test plan

- Production/Inspection schedule
- Standard form forms for inspection reporting such as
- Inspection documents listed in “Vendor Print Requirement”
- Procedure of certification
- Raw material source plan and Sub-VENDOR list
- etc.

Inspection/Witness testing requirements for level I and II will be agreed with VENDORS/SUBCONTRACTORS before award effective date, and finalized/agreed prior to commencement of fabrication at PIM to be initiated and coordinated by CONTRACTOR at VENDOR shop.

1.6 The witnessed inspection and tests being quoted shall be clearly identified in VENDOR’s proposal. Final acceptance of shop tests will be made under COMPANY/CONTRACTOR presence after the complete test sequence has been performed, but shall not constitute a waiver of the VENDOR obligation to provide complete Manufacturing items which meet all specified operating conditions.

1.7 If equipment has to be modified or repaired in order to pass final inspection and test, VENDOR shall compile a complete dossier containing accurate and detailed records of all design changes, alterations, modifications, adaptations and reasons for them, together with minutes of all relevant meeting and notes of all relevant discussions and shall promptly make such dossier available to CONTRACTOR.

1.8 Inspection Reports

Inspector’s reports shall be issued within ten(10) working days following the end of inspection by CONTRACTOR or TPA, with copy to COMPANY.

Such reports shall indicate in particular :

- P.O. number,
- Material inspected
- Nature of inspection and test performed
- Quantity accepted

- Quantity rejected with reasons
- All information about progress, quality, quantity, aspect

1.9 Certification

The equipment shall be provided with Certification Authority Certificate, which certifies that the equipment is suitable for use. (See CHAPTER D)

Accordingly, VENDOR shall provide submission procedure of certificates for approval, and the procedure will be finalized during pre-inspection meeting.

1.10 Quality Audit

CONTRACTOR QA and COMPANY QA reserve a right to audit VENDOR. And VENDOR shall prepare and submit the document requested.

2. Inspection Levels

2.1 Definition Of Inspection Levels

2.1.1. LEVEL I (Highest)

Inspection Level 1 is defined as a full stage inspection carried out progressively from commencement of manufacturing to final acceptance. This does not normally mean full-time witnessed in-line inspection during product manufacturing; however, this may be required on occasions where work program demands regular attendance. This shall include;

- Review/witnessing of source material's chemical and physical properties including metallurgical enhancement and traceability to approved certification level.
- Verify the use of qualified welders and qualified welding procedure.
- Monitor manufacturer's assembly, fabrication and erection and all prescribed tests.
- Check on materials, material traceability, dimensions and finishes.
- Scrutinize manufacturer's quality assurance/quality control system.
- Review/audit witness of non-destructive examinations including alloy verification if required. Ensuring that personnel are qualified to perform these examinations.
- Witness all pressure and performance tests followed by inspection of disassembled equipment, if applicable.
- Review/Witness all major tests required by APPROVED QA/QC VENDOR documents, including on and off load tests of machinery or type tests of electrical equipment as required.

- Final visual and dimensional inspection of equipment.
- Review of final data book package in accordance with approved index.
- Verify packing and marking identifications.
- Issue of Final Release Certificate(s).

2.1.2. LEVEL II

Inspection Level II is defined as specific stage inspection of equipment and final inspection of equipment prior to shipment. Stages of inspection shall be agreed upon during a pre-inspection meeting to be held with the VENDORS after purchase award and shall include:

- Scrutinize material test certificates
- Check at random of materials, dimensions, and finishes
- Monitor specific tests and stage inspections
- Auditing of the VENDORS' quality control program.
- Witnessing final pressure and workshop performance testing including on and off load tests as applicable and simulation of automatisms, followed by inspection of disassembled equipment if required.
- Final visual and dimensional inspection
- Review data book package in accordance with approved index.
- Verification of packing and marking.

2.1.3. LEVEL III

Inspection level III is defined as final condition or as built examination(s) and test(s). Inspection may be on one or more pieces of equipment or on a random batch selection and shall include:

- Review all quality control records for conformance.
- Witness final pressure and workshop performance testing including running tests, following by inspection of disassembled equipment, if required
- Final visual, dimensional and painting inspection.
- Review data book package in accordance with approved index.
- Verify packing and marking identification.
- Issue of Final Release Certificate(s).

2.1.4. LEVEL IV (Lowest)

Inspection Level IV is defined as the review and acceptance/endorsement of manufacturer attestation, including any data book requirements to approval index.

3. Inspection Visit Frequency

3.1 General

CONTRACTOR shall perform inspection visits in VENDORS' shops, as well as in their Sub-Vendors shops, at specific stages of equipment fabrication, assembly, testing, painting and packing. Such specific inspection stages are to be determined for each category of equipment in accordance with the finalized/approved inspection and test plan which identifies all inspection, NDT witnessing, and witness testing points applicable to all phases of fabrication, assembly and testing.

In addition to specific inspection visits, CONTRACTOR shall also conduct regular inspection visits in accordance with the frequencies indicated hereafter which are to be understood as minimum frequencies to be applied to each component of each equipment item.

Such frequencies are intended to cover inspection visits by professional inspectors only. CONTRACTOR shall not combine inspection and expediting functions, nor have them performed by the same individual.

3.2 Pressure Vessels, Heat Exchangers, Boilers

Level I : regular inspection visits shall be conducted at least once every month

Level II : regular inspection visits shall be conducted at least once every six weeks.

3.3 Major Machinery Equipment

Level I : regular inspection visits shall be conducted at least once every other week

Level II : regular inspection visits shall be conducted at least once every month

Level III: regular inspection visits shall be conducted at least once every six weeks.

3.4 Packages

Level I : regular inspection visits shall be conducted at least once every month

Level II : regular inspection visits shall be conducted at least once every six weeks.

3.5 Electrical/Instrumentation Equipment

Level I : regular inspection visits shall be conducted at least once every month

Level II : regular inspection visits shall be conducted at least once every six weeks

Level III: inspection visits at specific stages only.

3.6 Piping

Level I : regular inspection visits shall be conducted at least once every six weeks.

Level II/III : inspection visits at specific stages only.

3.7 (Later)

General Note: Specific Level I items shall require full time attendance by CONTRACTOR's resident representative(s), as identified in the attached list. Part time /full time attendance by CLIENT will occur at COMPANY's discretion.

4. Allocation Of Inspection Levels To Equipment & Materials

The descriptions of equipment and materials to be inspected are general.

ITEMS OF EQUIPMENT & MATERIALS TO BE INSPECTED					
ITEM NO.	DESCRIPTION	INSPECTION LEVELS			
		I	II	III	IV
1.0	PRESSURE VESSELS 1.1 Process, Injection, Accumulator drum, and pressurized storage vessels; BS5500 and ASME VIII, Div.2 ASME VIII, Div1 for design pressure And temperature conditions. - 80 bar.g or greater - less than 80 bar.g to 30 bar.g - less than 30 bar.g (except vacuum) and less than 340°C to 0 °C - less than 30 bar.g and above 340°C - less than 30 bar.g and below 0°C - under vacuum	 X X X X X X			
	1.2 Reactor Vessels, Driers, Columns	X			
	1.3 Impact tested carbon and low alloy steels, Hi Ni steel and austenitic stainless steels, Inconel lined	X			
	1.4 All services in low and cryogenic design temperatures	X			
	1.5 Non-ferrous Alloy Vessels	X			
	1.6 Cladded Vessels	X			
	1.7 Lined Vessels, rubber or epoxy coating	X			
	1.8 Slug-Catchers	X			

2.0	ATOMOSPHERIC PRESSURE STORAGE TANKS 2.1 Field fabricated carbon steel: - 25mm or greater - less than 25mm - impact tested carbon and low alloy steel, Hi Ni steel, S.S. and non-ferrous alloys	 X X X			
	2.2 Shop fabricated - carbon steel 35mm and greater - less than 35mm - fiberglass, lined, rubber or epoxy coated - alloy steels and non-ferrous alloys	 X X X	 X X		
3.0	BOILERS, FURNACES, BURNERS 3.1 Boilers, furnaces, burners, fired heaters	 X			
	3.2 Flares and Burners	X			
	3.3 Waste heat recovery boilers	X			
	3.4 Deaerators and steam drums	X			
4.0	EXCHANGERS 4.1 Shell and Tube for service: - 40 bar.g or greater - 1250mm bundle dia. or greater - less than 40 bar.g or 1250mm bundle dia. - low temperature (less than 0°C) - alloy or non-ferrous, or cladded - SOUR service - Cold Box	 X X X X X X X			
	4.2 Air coolers - headers, tube-bundles, fins - fans, motors, plenums, etc.	 X	 X		
	4.3 Double pipe, plate frame, spiral	X			
	4.4 Plate fin(core) exchangers	X			
	4.5 Cryogenic Exchangers	X			
	4.6 Cold Box	X			
5.0	ROTATING EQUIPMENT 5.1 Gas turbine driven and power generators:	 X			
	5.2 Electrically driven gas compressors	X			
	5.3 Pumps: - low and cryogenic temperatures - fire water, sea water - main but not critical - auxiliary pumps	 X X	 X	 X	
	5.4 Emergency generators	X			
	5.5 Air compressors	X			
	5.6 Miscellaneous - Boiler blower / Fans - Blowers, metering pumps, mixers - Manufacturer's standard items	 X		 X X	
	5.7 Diesel Engine Units	X			

6.0	PIPING AND PIPING MATERIALS 6.1 Piping: - impact tested carbon and low alloy steel, austenitic stainless steel and Inconel 625/Incoloy 825 - other piping		X	 X	
	6.2 Pipe flanges, fitting and valves: - impact tested carbon steel and low alloy steel, austenitic stainless steel and Inconel 625/Incoloy 825 - other flanges, fittings and valves		X	 X	
	6.3 Pipe supports, saddles, etc. - cryogenic temperatures - other services		X	X X	 X
	6.4 Metal bellow expansion joints - cryogenic temperatures - other services	X	 X		
	6.5 Bimetallic transition joints			X	
	6.6 Welding consumable/electrodes				X
7.0	STRUCTURAL 7.1 Special Category steel	X			
	7.2 First and Secondary Category steel		X		
	7.3 Tertiary steel			X	
8.0	SPECIAL EQUIPMENT 8.1 Process and utilities filter and strainers	X			
	8.2 Effluent treatment units		X		
	8.3 Chlorination package units		X		
	8.4 Desalination units	X			
	8.5 Nitrogen generation	X			
	8.6 Flare system incl. tips + ignition		X		
	8.7 Refrigeration units (HVAC)			X	
	8.8 Water treatment units		X		
	8.9 Incinerators		X		
	8.10 Chemical injection units		X		
	8.11 Sulphur granulation handling		X		
	8.12 Exhaust stacks		X		
	8.13 Lubricants, chemicals, resins, catalysts				X
	8.14 Overhead cranes, hoists		X		
	8.15 Lifting and Mobile Vehicles			X	
	8.16 Water maker (portable)			X	
	8.17 MEG/TEG Unit	X			
	8.18 Hydraulic power unit		X		
9.0	FIRE FIGHTING EQUIPMENT 9.1 Deluge/sprinker/C02/fixed skids		X		
	9.2 F/F Portables			X	
	9.3 Monitors		X		
	9.4 Hydrants, and piping system			X	
	9.5 Clothing				X
10.0	ELECTRICAL 10.1 Switch Gear		X		
	10.2 Motor control centres		X		

	10.3 Transformers: - 22Kv and higher or 300 kVA and above capacity - Less than 300 kVA capacity (low voltage)		X	X	
	10.4 Motors: - 1000kW and above rating - Less than 1000kW rating	X	X		
	10.5 Un-interruptible power supplies		X		
	10.6 Cables: - Power rated voltage 1kV and above - less than 1kV rating		X	X	
	10.7 Control Relay panels	X			
	10.8 Lighting fittings, junction boxes lighting and small panel, etc.			X	
	10.9 Batteries, chargers and distribution boards		X		
	10.10 Power distribution Control System	X			
	10.11 Emergency Generators	X			
	10.12 Air navigation aid beacons		X		
	10.13 Cable trays/cable ladders			X	
	10.14 Bus bar trunking			X	
11.0	TELECOMMS Telecommunication equipment - PA Systems - Telephone PABX - Intercommunication system - Radio systems, CCTV - others		X X X X X		
12.0	INSTRUMENTATION 12.1 Safety system PLCs (ESD, PSS, FG)	X			
	12.2 Control panels		X		
	12.3 Analyzers		X		
	12.4 Control valves/safety valves		X		
	12.5 Controllers, transmitters, recorders, etc			X	
	12.6 Gauges, pressure switches			X	
	12.7 Audio, visual alarming system		X		
	12.8 Metering and Tank gauging systems		X		
	12.9 Pressure control regulating skids		X		
	12.10 Flow meters, indicators (non-electrical)				X
	12.11 DCS/Supervisory computers	X			
	12.12 Gas chromatograph, sample conditioning systems, prefab. shelters		X		
	12.13 Cables-fibre optic cable		X		
13.0	MISCELLANEOUS 13.1 Equipment, materials or components not listed above			X	X

Attachment B1. Form of Shop Inspection and Test Plan

INSPECTION & TEST PLAN FOR SHOP	DISCIPLINE : VENDOR : DESCRIPTION :	ITP No. : Rev. No. : PAGE :	NO	DESCRIPTION OF INSPECTION/TEST	APPLICABLE SPEC. OR PROCEDURE	REPORTING FORMAT	PARTICIPATION BY: VENDOR	PARTICIPATION BY: CONTRACTOR/TPA	PARTICIPATION BY: COMPANY	REMARK

(LEGEND) P : PERFORMED R : REVIEW SW : SPOT WITNESS W : WITNESS H : HOLD

EXHIBIT

CHAPTER C. Work Scope of TPA

1. CONTRACTOR will appoint the services of TPA (Third Party Authorities) from the list set out in para. 5 of this CHAPTER to perform inspection and certification functions.
2. For the above services, CONTRACTOR shall provide full knowledge of the PROJECT contract requirements, specification, shop drawings and purchase order requirements plus applicable codes to TPA.
3. As one of CONTRACTOR's representative, TPA will perform the followings, but not be limited to;
   a. Quality Monitoring
   b. Visual Inspection
   c. Test witnessing at source of fabrication or manufacturing
   d. Reviewing vendor documents and procedures
   e. Verification of all Quality Control(Q/C) and Quality Assurance(Q/A) activities performed by the VENDOR to ensure compliance with purchasing specifications
4. The scope of the Certification TPA shall as a minimum accommodate
   1) Engineering Documents Approval :
      CONTRACTOR shall obtain all necessary design approval for the prefabrication if any and construction engineering of any heavy lifting or site movements design and procedures.
   2) CONTRACTOR ITEMS Reviews
      CONTRACTOR subject to review includes all material and equipment for which material certificates are required by relevant regulations.
      The review by the TPA will have to be performed, and certificate issued accordingly, before the material or equipment are released from VENDOR's WORKS.
   3) Fabrication work Approval
      CONTRACTOR shall obtain TPA's approvals for fabrication of the PLANT including:
      - Review of dossier for heavy lifting and site movements
      - WPS ,WPQT welders qualification
      - Heat treatment procedures and equipment
      - NDT equipment, procedures and specifications, NDT operators
      - Hydrotest equipment
      - NDT reports, hydrotest reports and the like
      - Witnessing of PSV calibration at SITE
      - Witnessing of load tests and functional tests of permanent lifting appliances on SITE

- Witnessing of all tests on SITE relating to boilers up to the popping test
- Witnessing of condensate tank gauging
- Witnessing any FAT of rotating equipment.
- Witnessing destructive test
- Witnessing corrosion test for slug catcher
- For BS 5500 vessels, TPA shall certify the design using FORM 'X'.
- Fire dampers : Fire test report to be signed by TPA.

4) Reporting

Throughout the period of TPA's involvement in the work, the TPA will issue to CONTRACTOR and COMPANY monthly report which describe:

- Progress
- Outstanding matters
- Problems arising from above

5) Close-out Report

The certification TPA shall issue to CONTRACTOR a close-out report with similar content to that of the CONTRACTOR's Close-out report, but covering only Certification TPAs Scope of Work

5. Approved Certification TPA by CONTRACTOR/COMPANY

1) LLOYD REGISTER
2) BUREAU VERITAS PARIS
3) DET NORSKE VERITAS
4) GERMANISHER LLOYDS
5) SOCIETE GENERATE DE SURVEILLANCE (SGS)
6) Other agencies : (to be informed later)

CHAPTER D. Material and Equipment Certification

1. Application

   This CHAPTER applies to the documentary certification requirement for materials and equipment and lays down the minimum acceptable standards for the format, nature and content of the certification supplied. In case of discrepancy and for omission and/or lack of information between this CHAPTER and the norm EN 10204 and Project Specification, this norm and those Project specifications will prevail.

2. Terms And Abbreviations

   - Certified Copy

     A copy of the original certificate which has been verified against the original by either the Originator, the Certification Authority, an inspector appointed by CONTRACTOR, or an independent inspector acceptable to COMPANY acting on behalf of the VENDOR, and which bears their original red stamp and signature.

   - Independent lifting appliance examiner

     A competent person authorized to conduct examination and testing of lifting appliances and gear acceptable to the Certification Authority.

   - Material

     Raw, manufactured or processed material.

   - Material Test Certificate

     A document which provides and attests to the results of tests on the material actually supplied, readily identifiable to, and recording the conformity of the material with the requirements of the code, standard or specifications given in the purchase order.

   - Original Certificate

     The actual certificate which was issued by the source manufacturer of the material and which bears the original stamps, signatures or endorsements of all relevant parties.

   - Special Category Steel

     All structural components of an Offshore installation, the failure of which would seriously endanger the safety of the installation, and as per the SPECIFICATIONS.

   - Purchase Order

     An order placed on a VENDOR or Contractor to manufacture materials or equipment in accordance with applicable statutory regulations, codes, standards and the project

specifications.

- Source

  Original place of manufacture of the material.

- Vendor

  A company appointed to supply materials or equipment in accordance with the terms and conditions of a Purchase Order.

3. Certification Type

Material certification shall be provided for all purchased items in accordance with the specific requirements of the purchase order. A matrix of certification Type against various materials and equipment is provided in Attachment D1, and certification Types quoted therein are defined below.

NOTE : All materials testing certificates shall be issued by VENDOR's QA/QC personnel who are not involved in the production process in manufacturing or processing works.

* TYPE A – EN 10 204 "3.1C"

Certificates confirming that the materials supplied conform to the delivery conditions of the Purchase Order and attested to by the Authority, COMPANY authorized Representative or Certification.

* TYPE B – EN 10 204 "3.1 B"

Certificates confirming that the materials supplied conform to the delivery conditions of the Purchase Order and/or in accordance with the official regulation and attested to by the VENDOR's authorized Representative.

* TYPE C – EN 10 204 "2.2" and "2.3"

Reports provided by the VENDOR in accordance with the requirement of the order and/or official regulation and/or corresponding technical rules.

EN 10 204 "2.3"

Specific Test Report issued on the basis of specific inspection and testing carried out on the products actually supplied mentioning the test results in accordance with the order

and/or official regulation and corresponding technical rules.

EN 10 204 “2.2”

Tests Reports issued on basis of non specific inspection and testing carried out on the products made from the same material and by the same manufacturing method as the product supplied and mentioning the test results.

TYPE D – EN 10 204 “2.1”

Certificates of Compliance issued by the VENDOR on the basis of non specific inspection and testing when tests results are not quoted but which testifies that the product supplied complies with the agreements made when the order was placed.

TYPE E – Type Approval

Certificates of type approval, type test and proof test.

4. Documentation

4.1 General

A material certificate shall be provided for each discrete piece or item of material or equipment. Where a number or pieces have identical batch number, heat/cast number, test number, and were manufactured at the same process and for the same purchase order item, then they maybe recorded on a single certificate.

Material certificates shall be the original documents except as subsequently defined.

For TYPE A and TYPE B applications, the material certificate supplied shall be the original document or a verified copy.

For materials where mechanical properties may have changed as result of subsequent processing, the certificates issued by the VENDOR shall be in accordance with TYPE B and shall contain source chemical analysis and manufacturer’s check analysis. Any transcription of the source material chemical analysis on to the VENDOR’s certificate shall be accompanied by the original or a

verified copy thereof.

'Stockists' certificates and 'typical' certificates are unacceptable.

Certificates and letters of conformity shall be signed by an authorized representative of the Vender's Quality Department.

4.2 Document Quality

a) All certificates shall be typed or printed. Handwritten certificates are unacceptable.

b) All certificates shall be in English language. Where this is not possible a notarized translation shall be provided.

c) All certificates shall be free from additions, deletions and corrections. The use of correction fluid is unacceptable

d) All certificates shall be of a clear, well contrasted and legible quality suitable for photocopying, microfilming or electronic imaging with reference to the following standards:

BS : 5536 Preparation of Technical Drawings and Diagrams for Microfilming

BS : 5444 Recommendations for the Preparation of Copy for Microfilming

BS : 4210 Specification for 35mm Microfilming of Technical Drawings

e) Each certificate shall carry as a minimum;

CONTRACTOR's purchase order number

Purchase order item number

Tag number (as applicable)

VENDOR's name and address

Signature of authority

VENDOR's verification signature

And additionally , where appropriate;

Applicable manufacturing code, standard or specification

Quality of material supplied against the order

Material/equipment description

Certificate number

Relevant test data

Heat, cost and batch number

VENDOR's serial number

Certification Authority endorsement

5. Material Test, Type Test(Proof Test & Type Approval Certificates)

5.1 General Requirements

5.1.1 In addition to the certification listed in para. 5.2, all equipment and materials released from VENDORs shall be accompanied by a copy (or copies) of;

a) CONTRACTOR's Inspection Release Certificate.

b) The Certification Authority inspection Release Note, where appropriate.

c) The letter or certificate of conformity from the VENDOR (Type D certificate) stating compliance with the applicable Order requirements.

d) Material test certificates for all items to be welded on site.

e) Outstanding Work Lists and QC punch listed items to be completed on site by the VENDOR and/ or fabrication CONTRACTOR.

f) Handling procedure, if required.

g) Packing, unpacking, storage and preservation procedure, if required.

h) Lubrication schedule (as appropriate).

i) Approved Vendor deviation requests.

5.1.2 Full details of the certification requirements of the Order are to be given in each Requisition.

5.2 Specific Requirement

5.2.1 General

a) Unless otherwise specified, or required by code or regulation, type test and type approval certificates shall be issued by an accredited independent test laboratory or authority acceptable to COMPANY and the Certification Authority. It shall be the VENDOR's responsibility to determine the acceptability or otherwise to the Certification Authority of the test laboratory or authority proposed.

b) Type test & type approval certificates shall be issued directly to the equipment Manufacturer by an accredited authority acceptable to COMPANY and the Certification Authority.

c) Type test and type approval certificates, together with any associated manufacturing licenses, shall be in date at the time of dispatch of the material/equipment to CONTRACTOR.

d) The list of material test, type test, type approval and proof test requirements which follow is not exhaustive. It shall be the VENDOR's responsibility to be aware of the requirements of the codes, standards and SPECIFICATIONS which apply to the order, and to implement them accordingly. Where doubt exists, CONTRACTOR shall seek guidance from COMPANY.

5.2.2 Special Category Steel

Special Category Steel shall be TYPE A endorsed by the Certification Authority.

5.2.3 Structural Steel

Structural steel plate, section, tubulars and castings for main members of pipe rack and structure shall be provided with TYPE B material test certification.

5.2.4 Electrical Appliances and Fittings

Certificates concerning suitability of appliances, enclosures, etc., for use in hazardous areas shall be issued by a nationally approved certifying body or nationally accredited laboratory acceptable to COPANY and the Certification Authority.

These certificates shall state the service, temperature class, gas group and zone classification for which the item is approved.

Drawings approved by the relevant certification body shall be made available for review/verification at the VENDORs works.

5.2.5 Passive Fire Protection

All passive fire protection systems, fire-rated architectural items and fire dampers which form part of a fire boundary shall be of a type which is fire-tested and certified in accordance with the requirements of the relevant specifications.

For all fire-rated architectural items, including doors, windows, ceilings, bulkheads, partition, roller shutters, insulation, coating systems, piping/cable/ducting penetration systems, etc., together with HVAC fire dampers, either of the following shall be provided:

a) A Certification Authority approval certificate for prototype fire tests carried out on the item(s) under the witness of the Certification Authority.

or

b) A fire Certificate and supporting fire test report for tests on the item(s) conducted by an independent, nationally accredited fire-test laboratory whose certification is acceptable to the Certification Authority.

All such certification shall provide:-

a) A clear statement of the class of division for which the item is suitable.

b) Adequate reference to the original test specifications and drawings upon which the prototype test was performed.

c) A statement of the validity period of the certificate.

5.2.6 Fire Fighting Equipment(FFE)

Fire-fighting equipment shall be of a type which is currently approved by COMPANY

5.2.7 Pipe Fittings – General

As per Project specification (To be issued later)

5.2.8 Flexible Pipes and Hoses

Each discrete category hose shall be of a type acceptable to COMPANY and shall have a type test certificate which demonstrates that the hose and method of attachment of the end connections have together been type tested to the requirements given in Figure 1.

* Figure 1. Minimum Testing and Certification Requirements for Flexible Hoses

DUTY	PRODUCT	RATING	CODE	BURST PRESSURE
Power and Utility	Oil, water, chemicals, compressed air and gases and hydraulic fluids		SAE J5170B	4 x Working Pressure

Individual hoses shall be provided with hydrostatic pressure test certificates.

Type tests shall be performed either in the presence of the Certification Authority themselves, or by an independent, accredited test laboratory whose certification is acceptable to the Certification Authority.

The type test certification presented shall be applicable to the bore, pressure rating and materials of construction of the actual hose(s) supplied. Where such certification covers a range of hose size, pressure ratings and materials, the limits of this range shall be agreed with the Certification Authority and shall also be in accordance with the applicable code(s) specified.

5.2.9 Fire Safe Valves

All valves which have parts which can degrade or deform in the event of fire (and especially those having elastomeric seat or seal materials), and which are to be installed in hydrocarbon or fire water service (including hydrant valves), shall have relevant fire type test certification acceptable to COMPANY.

Fire tests shall be carried out in presence of a recognized independent Authority, or by an independent, accredited fire test laboratory whose certification is acceptable to the Certification Authority. It shall be the VENDOR's responsibility to determine the acceptability or otherwise to the Certification Authority of the test laboratory or authority proposed.

Fire test certification for valves shall be in accordance with the requirements of API 6FA, API 607, BS:6755 or other relevant codes as agreed with the CONTRACTOR and COMPANY.

The fire test certification presented shall be applicable to the bore, pressure rating and materials of construction of the actual valve supplied. Where such certification covers a range of valve size, pressure classes and body materials, the limits of this range shall be in accordance with the applicable codes specified.

All individual valves shall be provided with test certificates as required in Project Specification

5.2.10 Pressure Relief Devices

All pressure relief devices, including safety valves (PSV's),bursting discs and relief valves shall be of a type which has been satisfactory type testes to establish their discharge capabilities at their maximum rated design pressures and temperatures.

Such type test certification shall be in accordance with an accepted code or standard, and performed either in the presence of the certification Authority themselves, or by an independent, accredited test laboratory whose certification is acceptable to the Certification Authority.

5.2.11 Pressure Vessels

Pressure vessels shall be provided with a certificate of code compliance in respect of design and construction, eg; BS:5500 Form X in case of use of BS 5500 CODE, together with a Certification Authority certificate which certifies that the vessels is suitable for use.

5.2.12 Lifting Appliances

- General : All lifting gear and appliances shall be manufactured, tested and certified in accordance with the requirements of the Certifying Authority's Code for Lifting Appliances, or an alternative code or codes acceptable to COMPANY and the Certification Authority. All fixed lifting appliances shall be provided with individual proof load test certificates and appropriate deflection reports.
- Loose gear :All loose lifting gear, including hooks, blocks, slings, swivels, rings, chains, etc., shall have individual proof load test certificates. Wire ropes and chains shall have individual proof test and material certificates in accordance with the relevant code.
- Winches and tuggers : Winches and tuggers shall be supplied with a type approval certificate for each discrete type or arrangement.
- Man-riding winches and tuggers : Man-riding winches and tuggers shall be supplied with a type approval certificate conforming that the arrangement is of a type approved for man-riding.

- Pad eyes and lifting lugs : All fixed lifting points forming part of equipment and package skids, together with any loose lifting gear designed for routine handing of equipment during normal platform operation , shall be subject to a trial lift prior to delivery. The satisfactory execution of the trial lift shall be detailed in a report. All loose lifting gear shall be proof load tested and certified accordingly.

5.2.13 Level gauges

Level gauges and sight glasses to be used for measuring hazardous or combustible liquids except LPG products shall be either have a certificate of type approval issued by the Certification Authority , or shall be of a type which is acceptable to the Certification Authority in the proposed application and service.

Attachment D1. Certification Matrix

The matrix of material, type test, type approval and proof test requirements which follows is not exhaustive. It shall be the VENDOR's responsibility to be aware of the requirements of the codes, standards, procedures and SPECIFICATIONS which apply to the Order, and to implement them accordingly.

Full details of the certification requirements of the Order are to be given in each Requisition.

All materials and equipment shall be certified in accordance with the requirements of the codes, standards, specifications and procedures referenced in the Requisition and the Purchase Order.

In addition to the certification listed in the matrix which follows, all equipment and materials released from VENDORs shall be accompanied by a copy or copies of;

a) CONTRACTOR's Inspection Release Note

b) The Certification Authority Inspection Release Note, where appropriate

c) The letter of certificate of conformity from the VENDOR (Type D certificate) stating compliance with the appliance order requirements.

d) Materials test certificates for all items to be welded on WORKSITE.

e) Outstanding Work List and QC punchlisted items to be on WORKSITE by the VENDOR and CONTRACTOR.

f) Handling procedure, if required.

g) Packing, unpacking, storage and preservation procedure, if required.

h) Lubrication schedule (as appropriate).

i) Approved Vendor deviation requests

j) Spare parts / Documentation

ITEM	MATERIAL CERTIFICATION	REMARKS AND ADDITIONAL REQUIREMENTS
Special Category Steel	A	Material certificate TYPE A
Structural steel	B, D	Material certificate TYPE B
Mechanical and Electrical Equipment	B, D, E	Material certificates TYPE B for component materials as defined elsewhere in this table, TYPE D for compliance with order, TYPE E as required
Electrical Appliances and Fittings	C, D, E	BASEEFA or equivalent Type test certification, IP compliance
Electric cable	B, D, E	Cable test certificates for individual lengths, Type test certificate
Passive Fire Protection Insulation and Coatings	C, D, E	Fire test certificate, fire test report
Fire-rated Architectural items, eg: doors, windows, bulkheads, penetrations and transits	C, D, E	Fire test certificate, fire test report
ITEM	MATERIAL CERTIFICATION	REMARKS AND ADDITIONAL REQUIREMENTS
Fire Dampers	C, D, E	Fire test certificate, fire test report
Instruments-tagged and bulk	B, C, D, E	Material test certificate TYPE B or C, Type approval certificate
Life saving Appliances	B, C, D, E	Material test certificate TYPE B or C as appropriate, certificate to SOLAS regulations
Fire Fighting Equipment	C, D, E	Material test certificates TYPE B and C as appropriate for individual fittings, hydro-test certificates where appropriate
Piping-General	B, D	Material test certificate TYPE B
Pipe fittings-General	B, D, E	Material test certificate TYPE B and Type test certificate for burst/proof tests.
Structural Steel Castings for primary duty	A	Material TYPE A certificates to be endorsed by the Certification Authority or an accredited independent inspectorate as agreed by COMPANY
Flexible Hoses and Pipes in and other hydrocarbon service applications	B, D, E	Material test certificate TYPE B for end fittings, hydro-test on individual hoses, Type approval and fire test certificates
Flexible Hoses and Pipes in General Applications	B, D, E	Material test certificate TYPE B for end fittings, hydro-test on individual hoses, Type approval certificates
Valves; Fire-safe Type	A/B, D, E	Material test certificate for body and bonnet TYPE B generally, TYPE A for exotic materials, and trim TYPE C, hydro-test on body

		and seat, fire test certificate
Valves; ESD valves and SSIV's	A, C, D, E	Material test certificate for body and bonnet TYPE A and trim TYPE C, hydro-test on body and seat, Certification Authority Type test or approval certificate
Valves, Tagged and Bulk	A/B, C, D, E	Material test certificate for body and bonnet TYPE B generally, TYPE A for exotic materials and trim TYPE C, hydro-test on body and seat
ITEM	MATERIAL CERTIFICATION	REMARKS AND ADDITIONAL REQUIREMENTS
Pressure Relief Devices; PSV's and Relief Valves Control Valves	A, C, D	Material test certificate for body and bonnet TYPE A generally, TYPE A for exotic materials and trim TYPE C, hydro-test on body and seat, calibration certificate
Pressure Relief Devices; Bursting Discs	C, D, E	Material test certificate TYPE C, Type test certificate, batch test certificate
Pressure Vessels	B, D, E	Certification Authority certificates for code compliance
Lifting appliances of 10t SWL and above	A/B, C, D, E	Material test certificates for structural components in the load path TYPE A or B, slew rings, TYPE A, and for other components, TYPE B or C as appropriate, proof load and calibration test certificates, Type approval certificate
Loose Gear	C, D, E	Material test certificates, proof and Type test certificates
Man-riding Winches and Tuggers	B, D, E	Material test certificates, proof test certificates, Type approval/Type test certificates
Pad-eyes and lifting lugs on Equipment	B, D, E	Material test certificates, Type test certificate, trial lifting report
Level Gauges and Sight Glasses	C, D, E	Material test certificate, Type approval/Type test certificate

Attachment D2. Form of Certificate of Conformity

CERTIFICATE OF CONFORMITY

SOUTH PARS FIELD DEVELOPMENT PHASES 9 &10

CERTIFICATE NO. :
MATERIAL REQUISITION NO. :
PURCHASE ORDER NO. :
DESCRIPTION OF P/O :
SHIPMENT NO. :
VENDOR / MANUFACTURER :
PURCHASER :

ITEM NO.	DESCRIPTION OF ITEM	DESCRIPTION OF SUB-ITEMS (IF ANY)

EXHIBIT

We undersigned, hereby certify that the materials supplied and delivered as described above are fully in compliance with the followings:

The goods have been manufactured, tested and inspected in accordance with the requirements of the purchase order and specifications.
All dimensions in approved drawing have been strictly followed in manufacturing the goods.
The goods have been manufactured in accordance with the international practices and technical standards.
There are no known hidden flaws or defects in the plant and equipment due to faulty materials and / or workmanship.

VENDOR'S SIGNATURE DATE

ENCLOSED :

CHAPTER E. Inspection Coordination Procedure

1 General

1.1 If there is any conflict between the related specifications, code and standard, VENDOR shall immediately consult with CONTRACTOR in written form for clarification.

1.2 CONTRACTOR will employ TPA approved by COMPANY and inspection agency is able to perform the shop inspection on behalf of CONTRACTOR. CONTRACTOR shall make available to equipment TPA all needed information and allow full access to the work.

1.3 VENDOR shall be responsible for providing required quality document during procurement activities based on para 5.4 during the purchasing. These documents shall be reviewed/approved by CONTRACTOR or COMPANY.

1.4 VENDOR shall grant CONTRACTOR's/COMPANY's inspector free of access to VENDOR's/Sub-Vendor's shop or plant at reasonable time to verify progress and to witness inspection & test activities of related equipment/materials.

1.5 VENDOR shall be responsible for inspection/test of the equipment and materials including parts supplied by sub-vendors, and for submittal of vendor document package of sub-vendor items.

1.6 VENDOR shall ensure that material/part used by sub-vendor are purchased only from acceptable sources according to his QA/QC manual and purchase specification. Quality documents of sub-vendor items shall be reviewed by designated inspector of COMPANY/CONTRACTOR during visiting VENDOR's shop for inspection & test witness.

1.7 VENDOR shall offer not only inspection & test measuring tool but also assistant manpower and facility to decrease inspection time.

1.8 All inspection & test measuring tools shall be calibrated with valid calibration certificate and recorded on control log by VENDOR.

1.9 During visiting VENDOR's shop for inspection & test activities, designated inspectors of COMPANY and CONTRACTOR can carry out spot audits jointly with VENDOR's inspector to assure that all work of VENDOR shall be performed in accordance with VENDOR QA/QC manual.

1.10 The language used in all document, data and forms for inspection/test shall be English, if not specified specially.

1.11 Inspection or non-inspection by CONTRACTOR shall not relieve the VENDOR of its obligation for quality control activities and guarantee for workmanship or performance of equipment.

1.12 When TPA have a inspection schedule on overtime or holiday, TPA shall submit inspection schedule for approval prior to any inspection performing.

2 Inspection Notice And Work Flow

2.1 According to approved shop inspection & test plan (ITP), VENDOR shall notify the beginning date of the related inspection/test activities to CONTRACTOR at the date specified in below table. For the Type 1, after getting COMPANY's intention, CONTRACTOR will relay it to VENDOR immediately.

Type	Notice time	Remark
1. PIM, FAT, COMPANY Witness Point	Twenty one(21) days in advance	
2. Others	Fourteen (14) days in advance	

2.2 CONTRACTOR has a right to adjust the proposed inspection date(s) from VENDOR considering various factors or situations.

2.3 VENDOR shall never proceed with inspection & test activities designated by COMPANY/CONTRACTOR without advance notice or a written waiver from CONTRACTOR.

2.4 CONTRACTOR's inspector will visit VENDOR's shop at scheduled inspection date/time, witness inspection & test activities and review all related inspection/test results performed already by VENDOR according to shop inspection & test plan in conjunction with inspection requirements. If all inspection/test results are satisfactory, then designated inspector will leave his name/signature on each inspection/test record for witness evidence.

2.5 Witness of any inspection/test activities shall not be construed as acceptance of any said component/part of the equipment.

2.6 VENDOR shall provide designated inspector with approved drawing, procedure and other related data to assist COMPANY's/CONTRACTOR's inspections.

2.7 A pre-inspection meeting will be held between COMPANY, CONTRACTOR, TPA and VENDOR for critical item, if requested by any party.

2.8 The inspection & test report shall be prepared by VENDOR and co-signed by designated inspector after witness of inspection & test activities.

2.9 Verbal inspection notice is not acceptable and written inspection notice shall be sent to CONTRACTOR by mail or telex. using attached form, Attachment E1.

2.10 CONTRACTOR's inspector will prepare the inspection & surveillance report and submit to CONTRACTOR for follow-up/monitoring, when necessary.

3 Non-Conformance

3.1 When non-conforming items are found at VENDOR's shop during manufacturing and/or inspection, they shall be reported to CONTRACTOR immediately for appraisal and disposition.

3.2 All non-conformances with relevant proposal for resolution shall be submitted item by item to COMPANY for appraisal.

3.3 All repair work of non-conformance shall be inspected or reviewed by designated inspector according to resolvable method approved by CONTRACTOR and COMPANY.

3.4 No items shall be shipped while non-conformance(s) remained outstanding except COMPANY approval to clear at site under CONTRACTOR's and VENDOR's responsibility.

4 Release For Shipment

4.1 CONTRACTOR will notify VENDOR of shipping release through Inspection Release Note after final/packing inspection and review of Vendor Quality Documents with

"Certificate of Conformity" prepared by VENDOR.

4.2 VENDOR shall not ship any items of equipment without receiving written notice for shipping release.

4.3 When VENDOR is permitted to ship on condition to perform the following work at work site, VENDOR shall bear all cost and expense incurred by such work.

a) Additional and/ or modification work.

b) Repair and/ or inspection.

4.4 If COMPANY or his representative signs off on Inspection Release Note during shop inspection, VENDOR may ship the related equipment/material and after shipping, shall submit Vendor Quality Documents with "Certificate of Conformity" to CONTRACTOR.

No item shall be shipped until TPA has accepted the response from VENDOR or CONTRACTOR, when required.

5 Documentation

Incomplete, inaccurate or illegible documents will be the cause of rejection for related items until such time as satisfactory rectification has been effected.

5.1 Submittal of quality documents with "certificate of conformity." VENDOR shall prepare quality document with "certificate of conformity" and submit to CONTRACTOR through normal channel.

5.2 Two(2) copies of Vendor Quality Documents shall be available for review by CONTRACTOR for issue of Inspection Release Note.

5.3 Contents of Vendor Quality Documents.

Quality documents shall include the following documents and records as a vendor document, but not be limited to. (See Vendor Document Requirement Schedule)

a) Certificate of Conformity

b) Material certificate.

c) Visual/Dimension check report

d) Nondestructive examination record

e) Pressure test certificate

f) Mechanical running/performance test records (with curve)

g) FAT report

h) Functional test report

i) Heat treatment records

j) Painting inspection report

k) Other test records/certificates, if applicable.

6 Attachments

E1. Inspection Application (Form. No.)

E2. Inspection Release Note (Form. No.)

E3. Non-Conformance Report (Form. No.) → **To be proposed later**

E4. Inspection & surveillance report. (Form. No.) → **To be proposed later**

ATTACHMENT E1. Form of Inspection Application

INSPECTION APPLICATION

FOR VENDOR

PREP'D	CHK'D	APP'D

DOCUMENT NO. :
ISSUE DATE :

ATTN.		E-MAIL :
CC		FAX NO. : +
		TEL NO. : +
FROM(VENDOR)		TEL NO. :
PJT. NO./NAME		
INSPECTION DATE & LOCATION	INSP. DATE : FROM _____ TO _____	FAX NO. :
	LOCATION :	TEL NO. :
	CONTACT PERSON :	

APPLICATION INFORMATION (Shall include review of prior insp reports)

P.O NO.	ITEM NAME	QT'Y	KIND OF INSPECTION

EXHIBIT

VENDOR DOC'T APPROVAL STATUS FOR EXECUTION OF APPLIED INSPECTION

KINDS OF VENDOR DOC'T (DWG, DS, ETC)	APPROVAL CODE	APPROVAL DATE

VENDOR'S INSP. DATE		RESULT	
WORK PROGRESS	%	□ FINAL(ALL/PARTIAL/BALANCE) □ INTER-INSP □ RE-INSP	
CONTRACT SHIPPING DUE DATE		ACTUAL EST. SHP'G DATE	

1. This application shall be submitted 2 WEEKS prior to the inspection due date.
2. All the required VENDOR documents shall be approved or approved as noted as a minimum, and shall be described in this application. No inspection shall be applied without approval of Vendor documents.
3. All required drawings, procedures, specifications and NCR, inspection records shall be prepared to PURCHASER's inspector before starting inspection.

FOR CONSOTIUM USE

ASSIGNED INSPECTOR : _____

COMMENTS :	CHECKED	APPROVED
DISTRIBUTION :		

ATTACHMENT E2. Form of Inspection Release Note

IRN

NO. : - -

INSPECTION RELEASE NOTE

WE HEREBY CERTIFY THAT THE UNDERMENTIONED COMMODITY HAS SATISFACTORILY PASSED THE TEST & INSPECTION AS NOTED IN ACCORDANCE WITH THE CONTRACTURAL SPECIFICATION. HOWEVER, THIS IN NO WAY RELEASES VENDOR OF HIS RESPONSIBILITY TO MEET THE REQUIREMENTS OF ALL SPECIFICATIONS AND DRAWINGS.

PROJECT NO. : 7O07	**PROJECT NAME : SP Phase 9&10**
CLIENT : POGC	**SITE : Assaluyeh, IRAN**
VENDOR :	**CONTACT :**
INSP. DATE :	**INSP. PLACE :**

P.O NO.	COMMODITY / ITEM NO.		RELEASED FOR			
			1	2	3	

LEGEND 1 : PARTIAL 2 : COMPLETE 3 : BALANCE

PARTIAL P.O - % RELEASE BY THIS IRN _____ % | TOTAL % RELEASE TO DATE _____ %

CONDITION

1. VENDOR :

2. CONSORTIUM :

EXHIBIT

ATTACHMENT

PREPARED BY : _____

CONFIRMED BY : _____

NOTES :
- **VENDOR IS NOT PERMITTED TO SHIP ANY GOODS WITHOUT INSTRUCTIONS FOR SHIPMENT FROM PURCHASER.**
- **FOR GOODS CONDITIONALLY ACCEPTED VENDOR TO PROVIDE EVIDENCE THAT CONDITIONS ARE MET PRIOR TO SHIPMENT.**

DISTRIBUTE TO : VENDOR / SITE / PM / PROC. / CLIENT

ATTACHMENT E3. Form of Non-Conformance Report

(Later)

ATTACHMENT E4. Form of Inspection & surveillance report.

(Later)